



# NAGAR PALIK NIGAM BHILAI

## NIT

पार्षद निधि अंतर्गत वार्ड क्र.-27 शास्त्री नगर बी.एम. शाह अस्पताल के पास एवं शासकीय प्राथमिक शाला के पास नवीन सीमेंटीकरण मार्ग नाली सहित निर्माण कार्य।

(As per P.W.D BUILDING/ROAD S.O.R. W.E.F. 01.01.2015)

S.N	PARTICULAR	Q	U
1	Excavation for all types and sizes of foundations, trenches and drains o.....m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	3.84	cum
2	Providing and laying nominal mix cement concrete with crushed ..... form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	0.48	cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using .. reinforcement and form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1.38	cum
4	Providing and placing in position reinforcement for R.C.C. work including .. drawings including cost of binding wire in foundation and plinth all complete:Thermo-Mechanically treated bars FE 415	55.20	kg
5	Providing and fixing formwork including entering ..... Foundations, footings, base of columns and plinth beam in any shape and size.	10.80	sqm
6	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads		
	P.C.C. M-25	45.00	cum
	P.C.C. M-30	67.50	cum
7	Carriage by mechanical transport for 5 km lead:		
	Earth	3.84	cum
 ASSISTANT ENGINEER NAGAR PALIK NIGAM, BHILAI		 SUB ENGINEER NAGAR PALIK NIGAM, BHILAI	