

**MUNICIPAL CORPORATION BHILAI (C.G.)****NIT****Name of work :-** वार्ड कं. 69 एव वार्ड कं. 70 हुडको के विभिन्न स्थानों में सिवर लाईन चेम्बर में ढक्कन संधारण कार्य।

As per Building SOR 01.01.2015

S.N o.	Description and details of work	Qty.	unit
1	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of form work 1:1 1/2:3 (1 cement : 1 1/2 coarse sand : 3 graded stone aggregate 20 mm nominal size). Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.	44.4	Cum
2	Providing and placing in position reinforcement for RCC work including straightening cutting, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete Thermo-Mechanically treated bars FE 500D	3552	Kg

**Asstt. Engineer  
Municipal Corporation  
Bhilai(C.G.)**



**Sub Engineer  
Municipal Corporation  
Bhilai (C.G.)**