

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

कार्य का नाम :- मुख्य कार्यालय में ट्रांसफार्मर के पास कटआउट एवं केबल लगाने

| S.N | Description and details of work | Unit | Qty |
|-----|--|-------|-----|
| 1 | Supplying and laying following sizes one number FRLS PVC insulated/XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground at a depth not less than 40 cm and upto 90 cm including excavation, sand cushioning, protective covering and refilling the trench etc as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1). | | |
| | 3.5 x 95 sq. mm. | Metre | 80 |
| 2 | Providing and fixing porcelain re-wireble fuse carrier and base unit on wooden board including drilling holes on the board, screws, connections etc. as per specification. (Thimbeling shall be paid separately). | | |
| | 300 amps | Each | 12 |
| 3 | Providing and fixing metal clad, TP&N double break fuse switch unit (HRC), 415/500 volts, with H.R.C. fuses including drilling holes on the board, connections, earthing the body etc. as per specification. (Thimbeling shall be paid separately). | | |
| | 200 amps | Each | 4 |
| 4 | Providing and fixing knife (DIN) type following H.R.C. fuses, with 80 KA breaking capacity in existing SFU/ FSU including bolts and nuts etc. as per specification. | | |
| | 200 amps | Each | 16 |
| 5 | Supplying and fixing wall mounted metal board of welded construction, fabricated with minimum 35 mm X 35 mm X 6 mm angle iron frame work, with 25 mm X 6 mm flat iron as intermediate members including painting etc. as per specification. | sqm | 4 |


Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai