

MUNICIPAL CORPORATION OF BHILAI

2

NIT


वार्ड क्र. 39 सुभाष नगर, स्वीपर मोहल्ला में अटल आवास का संधारण कार्य।

(As Per PWD Building SOR 01.01.2015 & Electrical SOR 01.06.2020)

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	6.60	Cum
2	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar	4.54	Cum
3	Dismantling lime/ cement plaster or skirting at any height raking out joints and cleaning the surface for plaster including disposal of rubbish within 50 metres lead.	300.00	Sqm
4	Demolishing cement concrete including disposal of material within 50 metre lead. 1:4:8 or leaner mix	10.98	Cum
5	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	27.17	Cum
6	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	1.94	Cum
7	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	13.200	Cum
8	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). + Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	31.800	Cum
9	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	3600.00	Kg
10	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:	44.00	Sqm
(A)	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.		
(B)	Beams, lintels, cantilevers & walls	26.40	Sqm
(C)	Columns, Pillars, Piers and likes- rectangular or square in shape	12.00	Sqm
(D)	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	90.40	Sqm
11	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	9.60	Sqm
12	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	7.68	Cum
13	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) + Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	13.44	Cum
14	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	704.00	Sqm
15	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:5	360.00	Sqm

S.N.	PARTICULARS OF ITEMS	Quantity	Unit
16	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement mortar 1:5	360.00	Sqm
17	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	151.20	Kg
18	Wall painting with premium emulsion (plastic) manufactured with the cow dung processing emulsion paint of required shade to give an even shade. On new work (two or more coats)	1064.00	Sqm
19	Painting exterior surface with SMOOTH exterior emulsion paint manufactured with th cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with : On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over)	360.00	Sqm
20	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	43.74	Sqm
21	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. Size 300x300mm	28.80	Sqm
22	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.	14.40	Sqm
23	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 50 mm Thick	255.00	Sqm
24	Add 15% For Electrification, Water Supply & Sanitary Work	130498.00	LS


Executive Engineer
 Municipal Corporation
 Bhilai


Assistant Engineer
 Municipal Corporation
 Bhilai


Sub Engineer
 Municipal Corporation
 Bhilai