

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र.-24 शासकीय प्राथमिक शाला हाउसिंग बोर्ड (22100722606) में अतिरिक्त कक्ष निर्माण कार्य।


(As Per PWD Building SOR 01.01.2015 & Electric SOR 01.06.2020)

| S.N. | PARTICULERS OF ITEMS | Quantity | UOM |
|------|---|----------|-----|
| 1 | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils. | | |
| | | 41.72 | Cum |
| 2 | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size). | | |
| | | 4.07 | Cum |
| 3 | Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work. 1:1 ½ :3 (1 cement : 1 ½ coarse sand : 3 graded stone aggregate 20mm nominal size) | | |
| | | 35.44 | Cum |
| 4 | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:Thermo-Mechanically treated bars. | | |
| | | 3189.56 | Kg |
| 5 | Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: | | |
| (a) | Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level. | | |
| | | 47.80 | Sqm |
| (b) | Columns, Pillars, Piers and likes- rectangular or square in shape | | |
| | | 16.58 | Sqm |
| (c) | Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ) | | |
| | | 119.16 | Sqm |
| (d) | Beams, lintels, cantilevers & walls | | |
| | | 53.60 | Sqm |
| 6 | Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) | | |
| | | 6.92 | Cum |
| 7 | Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) + Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth: | | |
| | | 32.37 | Cum |
| 8 | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete. | | |
| | | 53.83 | Cum |
| 9 | Providing & Laying damp proof course (up to 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including formwork. | | |
| | | 0.96 | Cum |
| 10 | Providing and fixing sliding shutter with M.S. sheet 1mm thick, frame and diagonal braces of 40x40x6mm angle iron, 3.0 mm thick M.S. gusset plates at junctions and corners, 25mm dia pulley, 40x40x6mm angle and T-iron guide at top and bottom respectively including applying a priming coat of red oxide zinc chromate primer. | | |
| | | 191.40 | Kg |
| 11 | Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer. | | |

| | | | |
|----|---|--------|-----|
| 12 | Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rails of T-iron 40x40x6mm with 38mm steel pulleys complete with bolts, nuts, locking arrangement stoppers, handles including applying a priming coat of red oxide zinc chromate primer | 182.25 | Kg |
| 13 | Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand) | 5.25 | Sqm |
| 14 | Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand) | 127.26 | Sqm |
| 15 | Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand) | 238.92 | Sqm |
| 16 | Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete. | 156.78 | Sqm |
| 17 | Providing and applying 2mm thick ready mix exterior grade putty (Manufactured with cow dung processing) on walls to make the surface smooth and even. | 88.62 | Sqm |
| 18 | Wall painting with premium emulsion (plastic) manufactured with the cow dung processing emulsion paint of required shade to give an even shade. On new work (two or more coats) | 288.16 | Sqm |
| 19 | Painting exterior surface with SMOOTH exterior emulsion paint manufactured with th cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with : On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over) | 288.16 | Sqm |
| 20 | Painting on new work (two or more coats) to give an even shade with: Premium synthetic enamel paint | 156.78 | Sqm |
| | | 32.40 | Sqm |



ASSTT.ENGINEER
Nagar Palik Nigam, Bhilai



SUB ENGINEER
Nagar Palik Nigam, Bhilai