



## NAGAR PALIK NIGAM BHILAI

### NIT

जोन क्र.-02 वैशाली नगर क्षेत्रांतर्गत सीवर चेम्बर ढक्कन संधारण कार्य।

(As per P.W.D.BUILDING S.O.R. W.E.F. 01.01.2015)

S.NO	PARTICULAR	Qty	Unit
1	Providing and laying nominal mix reinforced cement concrete with crushed stone ...20mm nominal size).+ Extra for precast PCC/ RCC work of any mix including form .. 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.		
		50.40	Cum
2	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:		
	Thermo-Mechanically treated bars FE 415	3024.00	Kg
			
ASSTT.ENGINEER		SUB ENGINEER	
Nagar Palik Nigam, Bhilai		Nagar Palik Nigam, Bhilai	