


MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

जोन क्रमांक 01 अंतर्गत स्थित सार्वजनिक स्टैण्ड पोस्ट का प्लेटफार्म संधारण कार्य।

Pwd Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	14.00	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	14.00	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	38.22	Cum
4	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape	389.20	Sqm
5	25mm thick cement concrete flooring with 1:2:4 cement concrete (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size) finished with floating cost of neat cement.	252.00	Sqm



Executive Engineer
Municipal Corporation
Bhilai (C.G)



Asstt. Engineer
Municipal Corporation
Bhilai (C.G)



Sub. Engineer
Municipal Corporatio
Bhilai (C.G)