

कार्यालय, नगर पालिक निगम, भिलाई निविदा सूचना


क्रमांक/लो.क.वि./जोन-1/ 2119

भिलाई, दिनांक 15/03/24

आयुक्त नगर पालिक निगम भिलाई की ओर से लोक निर्माण विभाग में पंजीकृत ठेकेदारों से लोक निर्माण विभाग के भवन एस.ओ.आर. दिनांक 01.01.2015 एवं सड़क एस.ओ.आर. दिनांक 01.01.2015 से लागू एवं अद्यतन संशोधन के आधार पर कम/अधिक एवं आयटम दर पर निम्नांकित कार्य दिनांक 08.04.2024 को सायं 5.30 बजे तक मुहरबंद निविदा आमंत्रित की जाती है। प्राप्त निविदा दिनांक 09.04.2024 को प्रातः 11.00 बजे खोली जाएंगी। निविदा प्रपत्र हेतु आवेदन दिनांक 01.04.2024 को सायं 5:30 बजे तक निर्धारित राशि के साथ आवेदन स्वीकार किये जावेगा।

क्र.	कार्य का नाम	निविदा लागत लाख में	धरोहर राशि	निविदा प्रपत्र का मूल्य	समयावधि	ठेकेदार की श्रेणी
1.	वार्ड-17 नेहरू भवन का संधारण कार्य।	9.89	7500.00	750.00	90 दिन	द एवं प्रवर

नियम एवं शर्तें:- 1. सशर्त निविदा स्वीकार नहीं की जावेगी। 2. निविदा स्पीड पोस्ट अथवा रजिस्टर्ड डाक से स्वीकार किये जावेंगे। 3. धरोहर राशि कार्यपालन अभियंता /जोन आयुक्त, नगर पालिक निगम, भिलाई एवं संबंधित ठेकेदार के नाम से तथा प्रत्येक कार्य के लिये जीवित ठेकेदारी ई-पंजीयन, पेनकार्ड, आयकर, जीवित बैंक सालवेंसी प्रमाण, GST पंजीयन पत्र की सत्यापित प्रति लिफाफा "क" में प्रस्तुत करना है, एवं निविदा प्रपत्र दर सहित लिफाफा "ख" में प्रस्तुत करना होगा। 4. कर्मकार कल्याण उपकर अधिनियम लागू होगी। 5. सम्पूर्ण निविदा अथवा किसी भी अंश को स्वीकृत करने अथवा न करने का अधिकार निगम के पास सुरक्षित रहेगा। 6. नगर निगम की वाहनों से निर्माण कार्य हेतु पानी लेने पर देयक से 1 % राशि की कटौती की जावेगी, किन्तु निगम वाहनों से जल उपलब्ध कराने हेतु बाध्य नहीं रहेगा। निगम क्षेत्र के स्रोतों से स्वयं के वाहनों से पानी लेने पर 0.5 % की कटौती की जावेगी। 7. ठेकेदार द्वारा निविदा में अंको एवं शब्दों दोनों में स्पष्ट रूप से दरे प्रस्तुत करें नहीं किये जाने पर निविदा फार्म निरस्त किया जावेगा। 8. शासन के आदेश क्रमांक 19 दिनांक 04.06.2016 के सफल निविदाकार की निविदा दर निविदा राशि के 90% से कम होने की स्थिति में अंतर की राशि एफ.डी.आर. के रूप में संविदा के पूर्व जमा करना होगा। 9. शासन के निर्देशानुसार श्रमिकों से संबंधित कार्यों हेतु श्रमिकों का पी.एफ. कटौती किया जाना है तथा बैंको में खाता खोलकर सीधे उनके बैंक खाते में श्रमायुक्त द्वारा स्वीकृत दरों के अनुरूप प्रतिमाह राशि जमा किया जाना है। 10. प्रस्तुत दस्तावेज असत्य पाये जाने पर पंजीयन निरस्त कर, काली सूची में दर्ज करने की कार्यवाही की जावेगी। 11. यदि निगम द्वारा निर्धारित निविदा प्राप्ति की अंतिम तिथि/निविदा खोलने की तिथि को किसी अपरिहार्य कारणवश अवकाश घोषित होता है तो ऐसी स्थिति में अंतिम तिथि/खोलने की तिथि आगामी कार्य दिवस को माना जायेगा। 12. प्रत्येक कार्य के लिए पृथक-पृथक धरोहर राशि जमा करें एवं समयोजन की कार्यवाही नहीं होगी। 13. शासन के निर्देशानुसार G.S.T. एवं अन्य कर सम्मिलित रहेगा। 14. निविदा में भाग लेने वाले इच्छुक एजेंसी प्रत्येक कार्य के लिए राशि रु. 100.00 स्टाम्प एफिडेविट संलग्न करना अनिवार्य होगा। 15. किसी भी विवाद स्थिति में आयुक्त/जोन आयुक्त नगर पालिक निगम, भिलाई का निर्णय अंतिम एवं मान्य होगा। विस्तृत जानकारी कार्यालयीन समय एवं तिथि में कार्यालय नगर पालिक निगम भिलाई नेहरू नगर जोन-01, नगर निगम भिलाई की वेबसाइट www. bhilainagarnigam.com अथवा संचालनालय की वेबसाइट www.uad.cg.gov.in एवं चीप्स की वेबसाइट eproc.cgstate.gov.in से देखी जा सकती है। 16. नियम एवं शर्तों अनुसार दस्तावेज संलग्न करें।


जोन आयुक्त
जोन-01
नगर पालिक निगम,
भिलाई

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT


कार्य का नाम :- वार्ड-17 नेहरू भवन का संचारण कार्य।


Pwd Building Sor 01.01.2015


S.No.	Description and details of work	Qty.	Unit
1	Removing white or colour wash by scrapping, sand papering and preparing the surface smooth including necessary repair to scratches etc. complete.	2427.15	Sqm
2	Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead	728.15	Sqm
3	Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required : White Orissa pattern W.C. pan of size 580x440 mm	3.00	Each
4	Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : White pedestal type	2.00	Each
5	Providing and fixing white vitreous china urinal basin with waste fitting as per IS : 2556, and other couplings in C.P. brass complete: Flat back half stall urinal of size 460x380x250mm	4.00	Each
6	Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required : White Size 550x450 mm	4.00	Each
7	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge.		
	25 mm nominal outer dia .Pipes.	50.00	Metre
	15 mm nominal outer dia .Pipes.	50.00	Metre
8	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.		
	150 mm dia pipe.	40.00	Metre
	110 mm dia pipe.	40.00	Metre
9	Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. Tee/ Tee with door/ Bend 45°/ Bend 90°	25.00	Each

10	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	1000.00	Litre
11	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.	66.15	Sqm
12	Providing and laying rectified ceramic glazed floor tiles of size 300x300mm and above conforming to IS : 15622 of approved make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. Size above 300x300mm	24.84	Sqm
13	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete. Size 600x600mm	233.31	Sqm
14	Providing and applying plaster of paris putty over plastered wall surface including scaffolding complete Upto 2 mm thickness to make surface even and smooth in line and level.	2427.15	Sqm
15	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	150.00	Kg
16	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	200.00	Kg
17	Painting exterior surface with TEXTURED exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On old work (One or more coats applied @ 1.82 ltr/ 10 sqm)	712.80	Sqm
18	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On old work (One or more coats applied @ 0.83 ltr/ 10 sqm)	1714.35	Sqm
19	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	450.00	Sqm
20	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	6.48	Cum
21	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	0.43	Cum
22	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size)	0.35	Cum

23	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	28.16	Kg
24	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	6.46	Sqm
25	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	4.84	Cum
26	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) + Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	2.60	Cum
27	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	0.72	Cum
28	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	3.20	Sqm
29	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:5 (1 cement : 5 fine sand)	18.90	Sqm
30	Providing and making 12mm thick cement plaster of mix : in C.M.-1:5 + Neat Cement punning.	24.44	Sqm
31	Providing, Laying and Jointing glazed stoneware pipes grade 'A' with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) i/c testing of joints etc. complete. 150 mm diameter	10.00	Metre
32	Add 5% For Electrification	47067.00	Rs


Executive Engineer
Municipal Corporation
Bhilai (C.G)


Asstt. Engineer
Municipal Corporation
Bhilai (C.G)


Sub. Engineer
Municipal Corporation
Bhilai (C.G)