

## MUNICIPAL CORPORATION BHILAI NIT

वार्ड क्र.-22 कुरुद डौर तालाब में रिटर्निंग वॉल एवं स्लेब संधारण एवं साफ-सफाई कार्य।

As per PWD Building/Bridge SOR, w. e. f. 01.01.2015 NON SOR ITEM

S NO.	PARTICULARS OF ITEMS	QUNTTY	UNIT
	[ Building sor w.e.f. 01.01.2015 ]		
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.		
	in all type of soil	52.00	Cu.M.
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.		
		39.00	Cu.M.
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.		
	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
	PCC Base	15.60	Cu.M.
4	Coursed rubble masonry (Second sort) with hard stone in Cement mortar 1:6 (1 cement : 6 coarse sand) upto plinth level.		
		78.00	Cu.M.
5	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.		
	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size). nominal size).		
		6.85	Cu.M.
7	Providing and making pointing on stone work with cement Mortar 1:3 (1 cement : 3 fine sand)		
	Flush pointing	149.50	Sq.M.
<b>NON SOR ITEM</b>			
1	Chain Excavator - (Fuel vehicle including driver and helper)		
		1nos x 4days	4.00 Nos
2	J.C.B. - (Fuel vehicle including driver and helper)		
		1nos x 4days	4.00 Nos
3	Dumper - (Fuel vehicle including driver and helper)		
		3nos x 4days	12.00 Nos

ASSTT.ENGINEER

Nagar Palik Nigam, Bhilai

*Ramg*

SUB ENGINEER

Nagar Palik Nigam, Bhilai