

9

MUNICIPAL CORPORATION BHILAI

NIT

कार्य का नाम :- वार्ड 36 नवीन प्राथमिक शाला के समीप सी.सी. एवं अन्य संघारण कार्य।

Based on PWD/SOR 1-01-2015 (building works) *Road S.O.R. 01.01.2015*

Item No.	Particulars of item	Qty.	Unit
1	2	7	9
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits	3.46	m ³
2	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:	11.18	m ³
3	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	102.00	m ³
4	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads)P.C.C. M-25	52.50	m ³

Rashmi

सहायक अभियन्ता
नगर पालिक निगम, मिलाई

अमित

उप अभियन्ता
नगर पालिक निगम, मिलाई