


MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम :- वार्ड 69 एवं वार्ड 70 हुडको के विभिन्न स्थानों में बैकलाईन सीवर लाईन चेम्बर में ढक्कन संधारण कार्य।

SN.	Details of Item	Qty.	Unit
1	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). + Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.F30	45.70	Cum
2	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	3455.08	kg



Asstt. Engineer
Municipal Corporation
Bhilai(C.G.)



Sub Engineer
Municipal Corporation
Bhilai (C.G.)