



# MUNICIPAL CORPORATION OF BHILAI

## NIT

कार्य का नाम :- वार्ड क्र. 66 सड़क 19 एवं सड़क 32 में नाली पुलिया संधारण कार्य।

SN.	Details of Item	Qty.	Unit
1	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil. @ Rs.185.00/m <sup>3</sup>	135.00	Cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size) @ Rs.2659.00/m <sup>3</sup>	15.00	Cum
3	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	175.00	Sqm
4	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	44.20	Sqm
5	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	1768.00	kg
6	Carriage by mechanical transport for 5 km lead.	108.00	Cum
7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	46.00	Sqm

  
Asstt. Engineer  
Municipal Corporation  
Bhilai(C.G.)

  
Sub Engineer  
Municipal Corporation  
Bhilai (C.G.)