

NAGAR PALIK NIGAM BHILAI

NIT

वार्ड क्र.-14 शांतिनगर सड़क 15, चंद्रनगर सड़क 10 एवं 14 में नाली संधारण कार्य।

(As per P.W.D BUILDING S.O.R. W.E.F. 01.01.2015)

S.N.	PARTICULAR	Q	U
1	Excavation for all types and sizes of foundations, trenches and drains o.....m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil		
		27.60	cum
2	Providing and laying nominal mix cement concrete with crushed form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
		13.80	cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using .. reinforcement and form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		32.20	cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:Thermo-Mechanically treated bars FE 415		
		1288.00	Kg
5	Providing and fixing formwork including entering ,..... Foundations, footings, base of columns and plinth beam in any shape and size.		
		368.00	sqm
6	Carriage by mechanical transport upto 5 km lead: Earth		
		19.32	cum

ASSTT.ENGINEER
Nagar Palik Nigam, Bhilai

SUB ENGINEER
Nagar Palik Nigam, Bhilai