

# MUNICIPAL CORPORATION BHILAI (C.G.)


## NIT

कार्य का नाम :- वार्ड-18 कान्स्ट्रक्टर कॉलोनी पुरानी बस्ती अजय मुर्गी फॉर्म, परदेशी चौक यादव कोचिंग के पास एवं महावीर गौतम घर के पास एवं बोरा लाईन में बोर खनन कार्य समबर्सिबल पंप सहित।


Pwd Building Sor 01.01.2015 & Electric Sor 01.06.2020 & Non Sor

S.No.	Description and details of work	Qty.	Unit
1	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge upto 90 metre depth below ground level. 125 mm dia.	100.00	Metre
	Rocky strata including Boulders. 125 mm dia.	260.00	Metre
2	Providing and fixing suitable size threaded mild steel cap or spot welded plate to the top of bore well housing/ casing pipe, removable as per requirement, all complete for bore well of: 150 mm dia	4	Each
3	Supplying, assembling, lowering and fixing in vertical position in bore well, ISI marked G.I. casing pipe (Plain) medium class in 4 to 7 meters length one end fitted with socket as per IS: 1239 (Part-1&Part-2) 1992 with IVth revision (Up-to-date amendments), of reputed & approved make, including required hire & labour charges, fittings & accessories, all complete, for all depths, as per direction of Engineer- in-charge. 125 mm nominal dia	104.00	Metre
4	Supplying, installation, testing and commissioning of submersible pump set for water supply system with submersible motor directly coupled to multi-stage submersible pump of specified discharge capacity, head, delivery size in existing bore well including 2 sets of suitable size holding clamps made out of 50 mm X 6 mm MS flat, connection with suitable submersible cable of standard length etc. as per specification and IS: 694 (2010). Note: submersible Cable should be rust proof, safe from oil / Grease and under water Chemical / abrasion Resistant. 3.00 HP, single phase	4	Each
5	Supply, installation, testing and commissioning of 1-3 HP 1 phase submersible motor starter cum control wall/ floor mounted type made out of not less than 1.6 mm thick MS sheet and comprising of following panel mounting switchgears there in including connection interconnection etc. as required. a) Phase indicating lamps with fuses and toggle switches 1 set b) 1/2/3 HP 1 phase DOL starter with over load and no volt relay 1 No c) 25 A "C" curve DPMCB 1 No d) Voltmeter 0-250 V 1 set	4.00	Each
6	Supplying, laying and fixing following size submersible cable along with GI/PVC/HDFC pipe line or laid in ground etc as per specification and IS: 694 (2010). Note: Cable should be rust proof, safe from oil / Grease and under water Chemical / abrasion Resistant.	200.00	Metre

S.No.	Description and details of work	Qty.	Ur.
7	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete		
	25 mm dia. nominal bore	400.00	Metre
	40 mm dia. nominal bore	240.00	Metre
	15 mm dia. nominal bore	120.00	Metre
	<b>NON SOR ITEM</b>		
1	Providing ISI Mark 50 mm dia Black H.D.P.E Roll Pipe with Bottom and Top Socket Assembly Fiting all Complete	200.00	Metre

  
**Executive Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Sub. Engineer**  
**Municipal Corporatio**  
**Bhilai (C.G)**