MUNICIPAL CORPORATION BHILAI

NIT

विषय – मुख्य कार्यालय एवं वाहन शाखा में सी.सी.टी.वी कैमरा लगाने हेतु।

S.N.	ITEM	QTY	CSIDC Rate	TOTAL
1	Network Bullet Cameras (5 MP Network Fixed Bullet Camera , 30 Mtr , WDR ,SD eard Support)	70		
2	Network Video Recorder (64 Channel Network Video Recorder - 8 Sata Port, 384 mbps bandwidth)	1		
3	Network Video Recorder (8 Channel Network Video Recorder - 8 Sata Port, 384 mbps bandwidth)	1		
4	Network Video Recorder (16 Channel Network Video Recorder - 8 Sata Port, 384 mbps bandwidth)	3		
5	Switches (8 Port PoE Giga Switch with 2 Giga Lan Uplink)	8		
6	Switches (16 Port Gigabyte PoE Switch + 2 SFP Port)	5		
7	Racks (6u Rack)	4		
8	Racks (4n Rack)	3		
9	CCTV surveillance system Accessories (Outdoor Double jacket Cat 6 Cable)	610		
10	CCTV surveillance system Accessories (Indoor Cat 6 Cable)	1815		
11	Hard Disk Storage Drive (HDD) (8 TB HDD)	1		
12	Hard Disk Storage Drive (HDD) (4 TB HDD)	4		
13	Installation Charges (Scope of installation & Dermissioning- Per Meter Laying of UTP lan cable with fixing of casing and capping/ PVC Pipe on wall or trus or pillar or as per site conditions, complete in all respects.)	3050		
14	Installation Charges (Scope of installation & amp; commissioning-Installation and commissioning of Dome /Bullet camera at designated place i.e on wall/ceilling/ Pole (fixing of mount, camera, complete Connection and Integration with system))	70		
15	Installation Charges (Scope of installation & Charges) (Scope of installation) (Scope	5		
16	Comprehensive Maintenance Charges for 12 Months (Scope of Comprehensive Maintenance- Preventive maintenance of Dome camera on wall/ceiling/Pole (repair / fixing of mount, camera, complete Connection and Integration with system)	70		
17	Comprehensive Maintenance Charges for 12 Months (Scope of Comprehensive Maintenance- Replacement and Laying of Per Meter Lying of UTP lan cable with fixing of casing and capping/ PVC Pipe on wall or truss or pillar or as per site conditions, complete in all respects.)	3050		
18	CCTV surveillance system Accessories (OFC Junction Box Fully Loaded)	70		

Asst. Engineer Municipal Corporation Bhilai Sub Engineer

Municipal Corporation

Bhilai