MUNICIPAL CORPORATION OF BHILAI

NIT

जोन क्र. 04 अंतर्गत सार्वजनिक स्थलों का संरक्षण हेतु बारबेड वायर फेंसिन्ग कार्य।

(As Per PWD Building SOR 01.01.2015)

s.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	44.28	Cum
2	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	1121.76	Kg
3	Providing and fixing in position G.I. barbed wire (93.8gram/m) to concrete/ wooden/ angle iron posts (straight or diagonal) including securing and screwing with G.I. tying wire, G.I. stapples, G.I.U-nails or steel pins etc., complete(Cost of posts, struts to be paid for separately)	3690.00	Metre
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement: 1½ coarse sand: 3 graded stone aggregate 20mm nominal size).	44.28	Cum

Executive Engineer Municiapal Corporation Bhilai

Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer Municipal Corporation Bhilai