

कार्य का नाम :- वार्ड 04 नेहरू नगर चौक के पास आधुनिक शौचालय का संधारण कार्य।

(As Per PWD Building SOR 01 01 2015 & Electric SOR 01 06 2020, Non Sor Item)

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.	40.00	Kg
2	Providing and fixing steel door made of angle iron of suitable sizes with M.S. grill of approved pattern made of M.S. flats or square or round bars coat of red oxide zinc chromate primer.	75.00	Kg
3	Providing, laying and jointing glazed stoneware pipes grade 'A' with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete : 100 mm diameter	20.00	M
4	Providing and constructing brick masonry road gully chamber 50x45x60cm with well burnt modular clay bricks crushing strength not less than 35kg/cm ² in cement mortar 1:4 (1 cement : 4 coarse sand) including 500 x 450 mm precast R.C.C. horizontal grating with frame complete as per standard design.	4.00	No.
5	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete 150mm thick as per standard design:100 mm diameter S.W. pipe	12.00	M
6	Providing and fixing sliding shutter with M.S. sheet 1mm thick, frame and diagonal braces of 40x40x6mm angle iron, 3.0 mm thick M.S. gusset plates at junctions and corners, 25mm dia pulley, 40x40x6mm angle and T-iron guide at top and bottom respectively including applying a priming coat of red oxide zinc chromate primer.	100.00	KG
7	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.	40.00	M
8	Neat Cement punning.	6.00	Sqm
9	Dismantling terrazzo or mosaic or glazed vitreous or patent cement or tiled flooring or dado skirting of any thickness without sub base.	52.20	Sqm
10	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	2.02	Cum
11	Dismantling doors chowkhats with shutters (steel or wood) including architrave, hold fast etc. complete and stacking within 50 metres lead.	10.00	Each

12	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	54.88	Sqm
13	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:	111.00	Sqm
14	Providing and making 12mm thick cement plaster of mix:	99.60	Sqm
15	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	0.54	Cum
16	Providing and constructing soak pit 1.20x1.20x1.20m filled with brickbats including S.W. drain pipe 100 mm diameter and 1.20 m long complete as per standard design.	3.00	Each
17	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).Extra for precast PCC/ RCC work of any mix	0.41	Cum
18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	2.37	Cum
19	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	32.40	KG
20	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size).	0.80	Cum
21	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. Size 300x300mm	3.60	Sqm
22	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and --- 12 mm thick bed of cement Mortar 1:3 -----cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm	19.20	Sqm
23	Distemping with acrylic washable distemper to give an even shade. On oldwork (two or more coats)	100.00	Sqm
24	Providing and fixing 10 litre capacity P.V.C. low level flushing cistern conforming to IS : 7231, with all fittings and fixtures complete. White	6.00	Each
25	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On old work (One or more coats applied @ 0.83 ltr/ 10 sqm)	196.80	Sqm

26	Painting on old work (two or more coats) to give an even shade with: Satin synthetic enamel paint	46.20	Sqm
27	Providing and fixing flexible P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. 32 mm dia	12.00	Each
28	Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required : White Orissa pattern W.C. pan of size 580x440 mm	3.00	Each
29	Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : White pedestal type	2.00	Each
31	Towel rail (600mm long x 20mm dia)	8.00	Each
32	Chequerred precast cement concrete tiles 22mm thick in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tile including cleaning of joint etc complete on 20 mm thick bed of cement mortar 1:4 (1 cement :4 coarse sand) : Ordinary cement without any pigment	13.50	Sqm
33	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.	50.00	KG
WATER SUPPLY WORKS			
34	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge.	20.00	M
35	Providing and placing on terrace (at all levels) polyethylene water storage tank ISI marked with cover and suitable locking arrangement and ---- holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	1000.00	Ltr
36	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: Bib cock (250 grams)	8.00	No
Rain water Harvesting			
37	Excavation for all types and size of foundation, trenches and drains or for any other purpose including disposal of ---- 1.5m. lift and lead upto 50m (at least 5m away from the excavated area). including dressing and leveling of pits.	3.38	Cum

38	Supplying, filling, spreading & leveling stone boulders/ Gravels/ Coarse sand, in recharge pit, in the required layers and thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge. (excavation of pit will be paid separately).	2.04	Cum
39	Providing and fixing 80-100 mm dia PVC ball valve for inlet/ outlet of rain water harvesting pipe and filter.	1.00	nos
40	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of form work 1:1 1/2:3 (1 cement : 1 1/2 coarse sand : 3 graded stone aggregate 20 mm nominal size). Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar, 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.	0.32	Cum
41	Half brick thick honey comb brick work with modular well burnt clay bricks of crushing strength not less than 25 kg/sqcm and water absorption not more than 20% upto plinth level.	6.75	Cum
42	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	60.00	KG
43	Electrification Work		
	As electric SOR 01.06.2020 Lum-Sum	15000.00	
44	NON SOR ITEM Slogan Painting & Informative board writing work.	75.00	Sqm

Executive Engineer
Municipal Corporation
Bhilai

Rashmi
Asstt. Engineer
Municipal Corporation
Bhilai

W
Sub Engineer
Municipal Corporation
Bhilai