

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

कार्य का नाम :- वार्ड-05 कोसानगर सांस्कृतिक भवन के पास सामुदायिक शौचालय का संधारण कार्य।

Pwd Building Sor 01.01.2015 & Elecetric Sor 01.06.2020, Non Sor


S.No.	Description and details of work	Qty.	Unit
1	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	1.70	Cum
2	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rails of T-iron 40x40x6mm with 38mm steel pulleys complete with bolts, nuts, locking arrangement stoppers, handles including applying a priming coat of red oxide zinc chromate primer.	5.25	Sqm
3	Providing, laying and jointing glazed stoneware pipes grade 'A' with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete :	42.00	Metre
4	Providing and constructing brick masonry road gully chamber 50x45x60cm with well burnt modular clay bricks crushing strength not less than 35kg/cm ² in cement mortar 1:4 (1 cement : 4 coarse sand) including 500 x 450 mm precast R.C.C. horizontal grating with frame complete as per standard design.	4.00	Nos
5	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 40 mm thick	60.00	Sqm
6	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete 150mm thick as per standard design: 100 mm diameter S.W. pipe	30.00	Metre
7	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	120.00	Kg
8	Providing and fixing steel door made of angle iron of suitable sizes with M.S. grill of approved pattern made of M.S. flats or square or round bars coat of red oxide zinc chromate primer.	210.00	Kg
9	Providing and fixing sliding shutter with M.S. sheet 1mm thick, frame and diagonal braces of 40x40x6mm angle iron, 3.0 mm thick M.S. gusset plates at junctions and corners, 25mm dia pulley, 40x40x6mm angle and T-iron guide at top and bottom respectively including applying a priming coat of red oxide zinc chromate primer.	150.00	Kg
10	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete. 110 mm dia pipe.	20.00	Metre
11	150 mm dia pipe.	20.00	Metre
12	Neat Cement punning.	30.00	Sqm
13	Dismantling terrazzo or mosaic or glazed vitreous or patent cement or tiled flooring or dado skirting of any thickness without sub base.	43.50	Sqm


S.No.	Description and details of work	Qty.	Unit	No.
14	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	2.02	Cum	Painting Satin sy
15	Dismantling doors chowkhats with shutters (steel or wood) including architrave, hold fast etc. complete and stacking within 50 metres lead.	12.00	Each	Provid confor
16	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	41.16	Sqm	Provi inclu
17	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:	111.00	Sqm	Provi OC
18	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:4 (1 cement : 4 fine sand)	99.60	Sqm	
19	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	1.08	Cum	
20	Providing and constructing soak pit 1.20x1.20x1.20m filled with brickbats including S.W. drain pipe 100 mm diameter and 1.20 m long complete as per standard design.	3.00	Nos	
21	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	2.37	Cum	
22	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.	0.81	Cum	
23	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	64.80	Kg	
24	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size)	1.20	Cum	
25	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.	3.60	Sqm	
26	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm	38.40	Sqm	
27	Distempering with acrylic washable distemper to give an even shade. On old work (one or more coats)	150.00	Sqm	
28	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:	196.80	Sqm	

S No.	Description and details of work	Qty.	Unit
29	Painting on old work (one or more coats) to give an even shade with: Satin synthetic enamel paint	34.65	Sqm
30	Providing and fixing 10 litre capacity P.V.C. low level flushing cistern conforming to IS : 7231, with all fittings and fixtures complete. White	6.00	Each
31	Providing and fixing flexible P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. 32 mm dia	8.00	Each
32	Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required :	4.00	Nos
33	Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS : 7231, with ll fittings and fixtures complete including cutting and making good the walls and floors wherever required : White pedestal type	4.00	Each
34	Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required : White Size 550x450 mm	3.00	Nos
35	Towel rail (600mm long x 20mm dia)	4.00	Each
36	Chequerred precast cement concrete tiles 22mm thick in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tile including cleaning of joint etc complete on 20 mm thick bed of cement mortar 1:4 (1 cement :4 coarse sand) : Ordinary cement without any pigment	13.50	Sqm
37	Designing, providing and fixing aluminium frame work made of special aluminium section on building face with M.S. angle iron brackets fixed on RCC structure with S.S. hold fasteners, including providing and fixing two sided structural adhesive tape of appropriate grade (NORTON or equivalent), on aluminium sections for fixing aluminium/ glass panel, sealing on periphery of frame work, by providing EPDM gasket, silicon weather sealant between aluminium frame and building structure including hire charges of double scaffolding complete.	80.00	Kg
38	Providing and fixing aluminium composite panels in approved panel sizes, thickness and shape on aluminium frame work on face of building. (Frame to be paid separately)	20.00	Sqm
39	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.	65.00	Kg
40	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. 15 mm nominal outer dia .Pipes.	48.00	Metre
41	25 mm nominal outer dia .Pipes.	48.00	Metre

S.No.	Description and details of work	Qty.	Unit
42	Providing and placing on terrace (at all levels) polyethylene water storage tank ISI marked with cover and suitable locking arrangement and --- holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	1000.00	Ltr.
43	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: Bib cock (250 grams)	20.00	Nos
Rain Water Harvesting			
44	Excavation for all types and size of foundation, trenches and drains or for any other purpose including disposal of --- 1.5m. lift and lead upto 50m (at least 5m away from the excavated area). including dressing and leveling of pits.	3.38	Cum
45	Supplying, filling, spreading & leveling stone boulders/ Gravels/ Coarse sand, in recharge pit, in the required layers and thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge. (excavation of pit will be paid separately).		
	Stone boulders of size range 5 cm to 20 cm, in recharge pit	0.68	Cum
	Gravels of size range 5 mm to 10 mm, over the existing layer of boulders	0.68	Cum
	Coarse sand of size range 1.5 mm to 2 mm over existing layer of gravel	0.38	Cum
46	Providing and fixing 80-100 mm dia PVC ball valve for inlet/ outlet of rain water harvesting pipe and filter.	1.00	Nos
47	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of form work 1:1 1/2:3 (1cement :1 1/2 coarse sand :3 graded stone aggregate 20 mm nominal size). Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.	0.32	Cum
48	Half brick thick honey comb brick work with modular well burnt clay bricks of crushing strength not less than 25 kg/sqcm and water absorption not more than 20% upto plinth level.	9.00	Cum
49	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	55.00	Kg
50	Electrification Work Lum-Sum	25000.00	Rs
Non Sor Item			
1	Slogan Painting & Informative board writing work.	75.00	Sqm

Executive Engineer
Municipal Corporation
Bhilai (C.G)


Asstt. Engineer
Municipal Corporation
Bhilai (C.G)


Sub Engineer
Municipal Corporation
Bhilai (C.G)