



NIT

NAME OF WORK- Repair of GSB APPROACH ROAD FOR
AVINASH METROPOLISH 58 AHP DU'S

ROAD WORK - 120 M length		PWD SOR- 01-01-2015 (Road)	
SN	REF.	ITEMS DESCRIPTION	QTY
1	3.2	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300	138 Cume.
2	4.1	Granular Sub-base as per Table:- 400-1	
		Construction of granular sub-base by providing graded Material,carriage of mixed Material to work site. spreading in uniform layers with motor grader on prepared surface watering, rolling and compacting with vibratory power roller at OMC to achieve the desired density, complete as per clause 401	
	B	By mix in place method	
	A	Plant mix method (with Mechanically crushed stone only)	
	(a)	For Lower Sub-base with	
	(i)	Grading-III Material	67.50
3	3.8	Removal of Unserviceable Soil with Disposal up to 1000 meters including loading and unloading	Cume.
		Transporation of excavated/compacted soil measured as per clause 301.8,.304.4 and 305.8	124.20
		for up to 5 km -----90% of exacavated soil	Cume.


SUB-ENGINEER
MUNICIPAL CORPORATION
BHILAI


ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI