

MUNICIPAL CORPORATION OF BHILAI


NIT

कार्य का नाम— जोन क्र. 05 क्षेत्रांतर्गत स्थित पावर पंपों में इलेक्ट्रीक पैनल में बॉक्स लगाने एवं संधारण कार्य।

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
1	Excavation for all types and size of foundation, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5m. lift and lead upto 50m (at least 5m away from the excavated area). Including dressing and leveling of pits. In all types of soil	10.4	Cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	2.40	Cum
3	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. 40 x40x 5	2424.80	kg
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1.5:3(1 cement : 1.5 coarse sand : 3 graded stone aggregate 40mm nominal size)	12.80	Cum
5	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	305.6	Sqm
6	12mm thick pre-laminated particle board flat pressed with decorative lamination on one side and balancing lamination on other side exterior Grade - I MDF Board 12 mm thick conforming to IS:14587,	9.20	sqm


Asstt. Engineer

Municipal Corporation
Bhilai(C.G.)


Sub Engineer

Municipal Corporation
Bhilai (C.G.)