

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

वार्ड क्र.- वार्ड-01 जुनवाणी चौहान ग्रीनवेली के बाजू न्यू सॉयल ग्रीन कॉलोनी में प्रधानमंत्री आवास योजना AHP साईट से पेयजल आपूर्ति हेतु डी.आई.पाईप लाईन बिछाने का कार्य।

(AS PER CG PHE S.O.R 2022-23)

S.No.	Description and details of work	Qty.	Unit
1	Providing, laying and jointing including testing following socket & spigot centrifugally cast (Spun) Ductile Iron pressure pipes with inside cement mortar lining (class K-7) conforming to IS: 8329/ 2000 with suitable Rubber Gasket (Push on) joints as per IS:5382/85 including testing of Joint (laying Conforming to IS 12288 :1987) 100mm	600.00	Rmt
2	Providing and Laying including testing ductile iron PN 16 type flanged sockets conforming to IS: 9523/2000 having dimension as per table 23 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining with finishing as per clause 13 of IS:9523/2000 100mm	8.00	Nos
3	Providing and Laying including testing ductile PN 16 type iron flanged spigot conforming to IS: 9523/2000 having dimension as per table 24 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining with finishing as per clause 13 of IS: 9523/2000,100mm	6.00	Nos
4	Providing and Laying including testing Ductile iron Mechanical joint collar with follower glands conforming to IS: 9523/2000 having dimension as per table 24 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen and internal cement mortar lining. 100mm	10.00	Nos
	150 mm	2.00	Nos
5	Providing and Laying including testing Ductile Iron All socket Tees conforming to IS:9523/2000 having dimension as per table 21 of IS:9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining with finishing as per clause 13 of IS: 9523/2000. 100mm x 100mm	4.00	Nos
6	Earth work in excavation for pipe trench in ordinary soil areas including dressing, watering, ramming and disposal of excavated earth lead up to 50m and lift up to 1.5m, disposal earth to be levelled, neatly dressed.	288.00	Cum
7	Pumping out water caused by springs, tides or river seepage, broken water mains or drains or well or the like.	112.00	KL
8	Filling available excavated earth in trenches, plinth sides of foundation in layers not exceeding 20cm. In depth including consolidation of each layer by ramming watering, lead up to 50m and lift up to 1.5m in all kinds of soils	240.00	Cum
9	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 m lead as per direction of engineer-in-charge. Nominal concrete 1:3:6 or richer mix (i.e equivalent design mix)	21.20	Cum
10	Providing and laying mechanically mixed cement concrete with crushed stone aggregate excluding centering and shuttering (with 40mm nominal size graded stone aggregate) 1:2:4 (M-15)	21.20	Cum
11	Labour only for cutting following Ductile Iron pipes of any type and class. 100 mm dia.	10.00	Per Cut

Executive Engineer
Municipal Corporation
Bhilai (C.G)

Asstt. Engineer
Municipal Corporation
Bhilai (C.G)

Sub Engineer
Municipal Corporation
Bhilai (C.G)

