



NAGAR PALIK NIGAM, BHILAI
NIT

वार्ड क्र.-28 प्रेमनगर क्षेत्रांतर्गत विभिन्न स्थानों के पुलिया संधारण कार्य।

(As per P.W.D BUILDING S.O.R. W.E.F. 01.01.2015)

S.NO	PARTICULAR	QTY	U
1	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	41.20	cum
2	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	12.36	cum
3	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	24.72	cum
4	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	190.55	cum
5	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	38.11	cum
6	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	38.11	cum
7	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work .1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	189.01	cum
8	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	22680.60	kg
9	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	1332.41	sqm
10	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	139.05	cum
	3x2		
11	Carriage by mechanical transport upto 5 km lead: Earth	134.42	cum
<p align="center"></p> <p align="center">ASSTT.ENGINEER</p> <p align="center">Nagar Palik Nigam, Bhilai</p>		<p align="center"></p> <p align="center">SUB ENGINEER</p> <p align="center">Nagar Palik Nigam, Bhilai</p>	