



# NAGAR PALIK NIGAM BHILAI

NIT

मूलभूत सुविधा अंतर्गत वार्ड क्र.-27 शास्त्री नगर प्रदीप किराना स्टोर्स से तालाब किनारे एवं सुनिता वर्मा गली में रोड,

नाली एवं पुलिया संधारण कार्य।

(As per P.W.D BUILDING/ROAD S.O.R. W.E.F. 01.01.2015)

S.N.	PARTICULAR	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains 0.....m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil		
		48.65	cum
2	Providing and laying nominal mix cement concrete with crushed ..... form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
		6.95	cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using .. reinforcement and form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		15.63	cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415		
		937.80	Kg
5	Providing and fixing formwork including entering ..... Foundations, footings, base of columns and plinth beam in any shape and size.		
		158.60	sqm
6	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		1.22	cum
7	Carriage by mechanical transport upto 5 km lead: Earth		
		34.06	cum
8	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads)		
	P.C.C. M-10	7.40	cum
	P.C.C. M-25	24.38	cum
			
	ASSTT. ENGINEER		
	Nagar Palik Nigam, Bhilai		
			
	SUB ENGINEER		
	Nagar Palik Nigam, Bhilai		