

# MUNICIPAL CORPORATION OF BHILAI

NIT

जोन क्र. 04 अंतर्गत वार्ड क्र. 49, श्रीराम चौक मैदान में स्थित सामुदायिक शौचालय का संधारण कार्य।

AS Per PWD Building SOR 01.01.2015 & Electric SOR 01.06.2020

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Providing, laying and jointing glazed stoneware pipes grade 'A' with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete : 100 mm diameter	10.00	Mtr.
2	Providing and constructing brick masonry road gully chamber 50x45x60cm with well burnt modular clay bricks crushing strength not less than 35kg/cm <sup>2</sup> in cement mortar 1:4 (1 cement : 4 coarse sand) including 500 x 450 mm precast R.C.C. horizontal grating with frame complete as per standard design.	1	No.
3	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 40 mm thick	4.00	Sqm
4	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete 150mm thick as per standard design:100 mm diameter S.W. pipe	3.00	Mtr.
5	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	30.00	Kg
6	Providing and fixing steel door made of angle iron of suitable sizes with M.S. grill of approved pattern made of M.S. flats or square or round bars coat of red oxide zinc chromate primer.	30.00	Kg
7	Providing and fixing sliding shutter with M.S. sheet 1mm thick, frame and diagonal braces of 40x40x6mm angle iron, 3.0 mm thick M.S. gusset plates at junctions and corners, 25mm dia pulley, 40x40x6mm angle and T-iron guide at top and bottom respectively including applying a priming coat of red oxide zinc chromate primer.	30.00	Kg
8	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete. 110 mm dia 150 mm dia	5.00 5.00	M M
9	Neat Cement punning.	3.00	Sqm
10	Dismantling terrazzo or mosaic or glazed vitreous or patent cement or tiled flooring or dado skirting of any thickness without sub base.	8.70	Sqm
11	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	0.34	Cum
12	Dismantling doors chowkhats with shutters (steel or wood) including architrave, hold fast etc. complete and stacking within 50 metres lead.	2	Each
13	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	4.20	Sqm
14	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)	6.30	Sqm
15	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:4 (1 cement : 4 fine sand)	6.30	Sqm
16	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	0.27	Cum

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
17	Providing and fixing 30mm thick fibreglass reinforced plastic (F.R.P.) flush door shutter in different plain and wood finish made with fire retardant grade unsaturated polyester resin, moulded to 3mm thick FRP laminate all around, with suitable wooden blocks inside at required places for fixing of fittings and polyurethane foam (PUF) / Polystyrene foam to be used as filler material throughout the hollow panel, casted monolithically with testing parameters of F.R.P. laminate conforming to table - 3 of IS: 14856 : 2000, complete.	1.80	Cum
18	Providing and constructing soak pit 1.20x1.20x1.20m filled with brickbats including S.W. drain pipe 100 mm diameter and 1.20 m long complete as per standard design.	2	Each
19	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	0.20	Cum
20	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).Extra for precast PCC/RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.	0.68	Cum
21	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	0.39	Cum
22	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	33.75	Kg
23	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size).	0.20	Cum
24	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	23.20	Sqm
25	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. Size 300x300mm	9.60	Sqm
26	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and --- 12 mm thick bed of cement Mortar 1:3 -----cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm	1.00	Sqm
27	Distemping with acrylic washable distemper manufactured with the cow dung processig to give an even shade. On old work (one or more coats)	5.04	Sqm
28	Painting exterior surface with SMOOTH exterior emulsion paint manufactured with th cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with : On old Work (One or more coats applied @ 0.83 ltr/ 10 sqm)	9.00	Sqm
29	Providing and fixing 10 litre capacity P.V.C. low level flushing cistern conforming to IS : 723 l, with all fittings and fixtures complete. White	2	Each
30	Painting on old work (two or more coats) to give an even shade with: Satin synthetic enamel paint	5.775	Sqm
31	Providing and fixing flexible P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. 32 mm dia	2	Each
32	Providing and fixing vitreous china water closet squatting pan (Indian type) including cutting and making good the walls and floors wherever required: White Orissa pattern W.C. pan of size 580x440 mm	1	Each

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
33	Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : White pedestal type	1	Each
34	Providing and fixing vitreous china wash basin with C.I. brackets, 32mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required : White Size 550x450 mm	1	Each
35	Towel rail (600mm long x 20mm dia)	2	Each
36	Chequerred precast cement concrete tiles 22mm thick in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tile including cleaning of joint etc complete on 20 mm thick bed of cement mortar 1:4 (1 cement :4 coarse sand) : Ordinary cement without any pigment	2.25	Sqm
37	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge.		
	15 mm nominal outer dia .Pipes.	5.00	Mtr.
	25 mm nominal outer dia .Pipes.	5.00	Mtr.
38	Providing and placing on terrace (at all levels) polyethylene water storage tank ISI marked with cover and suitable locking arrangement and ---- holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	1000.00	Ltr
39	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:		
	25 mm dia. nominal bore	5.00	Mt
	15 mm dia. nominal bore	5.00	Mtr.
40	Providing and fixing on wall surface G.I. pipes medium class complete with G.I. fittings and clamps, including cutting, making good the walls etc. and testing of joints complete: 25 mm dia. nominal bore	5.00	Mtr.
41	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end): 25 mm nominal bore	1	No
42	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: Bib cock (250 grams)	10	No
43	Providing and fixing aluminium composite panels in approved panel sizes, thickness and shape on aluminium frame work on face of building. (Frame to be paid separately) 4mm thick	38.40	Sqm
44	Designing, providing and fixing aluminium frame work made of special aluminium section on building face with M.S. angle iron brackets fixed on RCC structure with S.S. hold fasteners, including providing and fixing two sided structural adhesive tape of appropriate grade (NORTON or equivalent), on aluminium sections for fixing aluminium/ glass panel, sealing on periphery of frame work, by providing EPDM gasket, silicon weather sealant between aluminium frame and building structure including hire charges of double scaffolding complete.	115.20	Kg
45	Electrification Work	7000.00	LS

  
**Executive Engineer**  
Municipal Corporation  
Bhilai

  
**Assistant Engineer**  
Municipal Corporation  
Bhilai

**Sub Engineer**  
Municipal Corporation  
Bhilai