MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

कार्य का नाम :- जोन क्रमांक 01 नेहरू नगर अंतर्गत स्थित सामुदायिक शौचालय का संधारण कार्य।

Pwd Building Sor 01.01.2015 & Elecetric Sor 01.06.2020

S.No.	Description and details of work	Qty.	Unit
1	Providing, laying and jointing glazed stoneware pipes grade 'A' with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete :	40.00	Metre
2	Providing and constructing brick masonry road gully chamber 50x45x60cm with well burnt modular clay bricks crushing strength not less than 35kg/cm2 in cement mortar 1:4 (1 cement : 4 coarse sand) including 500 x 450 mm precast R.C.C. horizontal grating with frame complete as per standard design.	6.00	Nos
3	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 40 mm thick	40.00	Sqm
4	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete 150mm thick as per standard design: 100 mm	30.00	Metre
5	diameter S.W. pipe Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets,	100.00	Kg
6	gates and similar works. Providing and fixing steel door made of angle iron of suitable sizes with M.S. grill of approved pattern made of M.S. flats or square or round bars coat of red oxide zinc chromate primer.	480.00	Kg
7	Providing and fixing sliding shutter with M.S. sheet 1mm thick, frame and diagonal braces of 40x40x6mm angle iron, 3.0 mm thick M.S. gusset plates at junctions and corners, 25mm dia pulley, 40x40x6mm angle and T-iron guide at top and bottom respectively including applying a priming coat of red oxide zinc chromate primer.	200.00	Kg
8	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS: 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS: 5382 leaving 10 mm	40.00	Metre
9	gap for thermal expansion etc complete. 110 mm dia pipe. 150 mm dia pipe.	40.00	Metre
10	Neat Cement punning.	36.00	Sqm
11	Dismantling terrazzo or mosaic or glazed vitreous or patent cement or tiled flooring or dado skirting of any thickness without sub base.	104.40	Sqm
12	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	4.03	Cum
13	Dismantling doors chowkhats with shutters (steel or wood) including architrave, hold fast etc. complete and stacking within 50 metres lead.	24.00	Each
14	Providing and making 6mm thick cement plaster of mix:	82.32	Sqm

S.No.	Description and details of work	Qty.	Unit
15	Providing and making 15mm thick cement plaster on the rough side of	222.00	Sqm
16	single or half brick wall of mix: Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:4 (1 cement : 4 fine sand)	199.20	Sqm
17	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	2.16	Cum
18	Providing and constructing soak pit 1.20x1.20x1.20m filled with brickbats including S.W. drain pipe 100 mm diameter and 1.20 m long complete as per standard design.	8.00	Nos
19	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	1.60	Cum
20	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size)	2.40	Cum
21	Providing and laying ceramic glazed floor tiles conforming to IS: 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement: 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.	7.20	Sqm
22	Providing and fixing ceramic glazed wall tiles conforming to IS: 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm	96.00	Sqm
23	Distempering with acrylic washable distemper to give an even shade. On old work (one or more coats)	200.00	Sqm
24	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:	393.60	Sqm
25	Painting on old work (one or more coats) to give an even shade with: Satin synthetic enamel paint	69.30	Sqm
26	Providing and fixing 10 litre capacity P.V.C. low level flushing cistern conforming to IS: 7231, with all fittings and fixtures complete. White	8.00	Each
27	Providing and fixing flexible P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. 32 mm dia	16.00	Each
28	Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS: 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required:	8.00	Nos

S.No.	Description and details of work	Qty.	Unit
29	Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS: 7231, with Il fittings and fixtures complete including cutting and making good the walls and floors wherever required: White pedestal type	8.00	Each
30	Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required: White Size 550x450 mm	4.00	Nos
31	Towel rail (600mm long x 20mm dia)	8.00	Each
32	Chequerred precast cement concrete tiles 22mm thick in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tile including cleaning of joint etc complete on 20 mm thick bed of cement mortar 1:4 (1 cement :4 coarse sand): Ordinary cement without any pigment	27.00	Sqm
33	Providing stainless steel railing/grill made of S.S. flats, hollow S.S. pipe or square/rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.	50.00	Kg
34	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. 15 mm nominal outer dia .Pipes.	40.00	Metre
35	25 mm nominal outer dia .Pipes.	40.00	Metre
36	Providing and placing on terrace (at all levels) polyethylene water storage tank ISI marked with cover and suitable locking arrangement and holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	2000.00	Ltr.
37	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: Bib cock (250 grams)	48.00	Nos
38	Electrification Work Lum-Sum	44926.00	Rs

Executive Engineer Municipal Corporation Bhilai (C.G)

Asstt. Engineer **Municipal Corporation** Bhilai (C.G)

Sub. Engineer **Municipal Corporatio** Bhilai (C.G)