


NAGAR PALIK NIGAM BHILAI

NIT

निधि अंतर्गत वार्ड क्र.-14 शांतिनगर सड़क 22 एवं 23 में नवीन सीमेंट कांक्रीट मार्ग नाली सहित निर्माण कार्य।

(As per P.W.D BUILDING / ROAD S.O.R. W.E.F. 01.01.2015)

S.N.	PARTICULAR	Q	U
1	Excavation for all types and sizes of foundations, trenches and drains o.....m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil		
		52.80	cum
2	Providing and laying nominal mix cement concrete with crushed form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
		6.60	cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using .. reinforcement and form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		15.40	cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:Thermo-Mechanically treated bars FE 415		
		616.00	Kg
5	Providing and fixing formwork including entering ,..... Foundations, footings, base of columns and plinth beam in any shape and size.		
		88.00	sqm
6	Carriage by mechanical transport upto 5 km lead:		
	Earth	36.96	cum
7	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevantclauses of section 300.		
		10.80	cum
8	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads		
	P.C.C. M-10	3.60	cum
	P.C.C. M-25	10.80	cum
9	Transportation of metal i/c loading & unloading		
	For a lead upto 1 Km.	9.18	cum



ASSTT.ENGINEER
Nagar Palik Nigam, Bhilai

SUB ENGINEER
Nagar Palik Nigam, Bhilai