

6

MUNICIPAL CORPORATION BHILAI

NIT

कार्य का नाम :- वार्ड 56 सेक्टर 02 के सड़क 15 एवं 16 के बीच एवं सड़क 15 एवं 15 बी में नाली पुलिया संधारण कार्य।

As Per PWD Building SOR 01.01.2015

SN.	Details of Item	Qty.	Unit
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	1.20	Cum
2	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	1.00	Cum
3	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	1.80	Cum
4	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	43.20	Cum
5	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	4.32	Cum
6	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	19.38	Cum
7	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	969.00	Kg
8	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	4.80	Cum
9	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	132.00	Sqm
10	Carriage by mechanical transport for 5 km lead. Earth	45.40	Cum

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

~~उप~~ अभियन्ता
नगर पालिक निगम, भिलाई