

MUNICIPAL CORPORATION OF BHILAI


NIT

पार्षद निधि अंतर्गत जोन 02 खुरसीपार बाबा बालकनाथ गार्डन एवं गुरुद्वारा के पास भवन में नयी सुविधाएं प्रदाय कार्य।

(As Per PWD Building/Road SOR 01.01.2015 & Electrical SOR 01.06.2020)

SN	PARTICULERS OF ITEMS	QTY.	UNIT
1	Supplying, installation, testing and commissioning of following size drinking water cooler storage type ISI marked, eco friendly non CFC refrigerant, water tank and cooler cabinet sheet material- stainless steel {grade AISI 304} with thickness \geq 0.8 mm, with PUF insulation including all accessories connection etc complete as per specification. 150/300 Ltrs/hr	1	Each
2	Providing and fixing steel grid for false ceiling made from M.S. rectangular hollow tubes of 50x25x1.25mm (wall thickness) as main runners to be jointed to cross runners of same size by electric arc welding with spacing not exceeding 610x610mm in any direction. The frame to be screwed to the wall using wooden plugs and wood screws of size 50x8mm at an interval of not more than 300mm centre to centre. The grid to be supported using 6mm M.S. hanger bars at 1200mm centre to centre both ways bent, hooked, fixed to existing R.C.C. roof with fastener or to the truss as the case may be and bolted to the grid with the help of suitable M.S. holding cleats, complete.	280.00	Kg
3	Providing and fixing at all height false ceiling consisting of frame work "W" / "U" / "L" sections made of G.I. sheet with zinc coating of grade 120 consisting of angle cleats of size 25mm wide x 1.6mm thick with flanges of 22mm and 37mm at 1200mm centre to centre one flange fixed to the ceiling with dash fastener 12.5mm dia x 40mm long with 6mm dia bolts to the angle hangers of 25x25x0.55mm of required length, and other end of angle hanger being fixed with nut and bolts to G.I. channels 45x15x0.9mm running at the rate of 1200mm centre to centre to which the ceiling section 0.5mm thick button wedge of 80mm with tapered flanges of 26mm each having clips of 10.5mm at 450mm centre to centre shall be fixed in a ---- cost of painting	120.00	Sqm
4	Human and other sculptures (b) 2 to 5 feet	1	Sqm
5	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	0.36	Cum
6	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	0.12	Cum
7	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	0.240	Cum
8	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	24.00	Kg
9	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
(A)	Columns, Pillars, Piers and likes- rectangular or square in shape	9.00	Sqm
10	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	0.20	Cum
11	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:5 (1 cement : 5 fine sand)	12.14	Sqm
12	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.	80.00	Kg

SN	PARTICULERS OF ITEMS	QTY.	UNIT
13	15 mm thick Table rubbed polished Granite stone slab flooring laid over 20mm (Average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry including rubbing and polishing etc. complete. (Area of slab should be 0.50 sqm and above) Granite stone black	7.07	Sqm
14	15 mm thick Table rubbed polished Granite stone slab in risers and treads of steps skirting dado and pillars laid on 12mm (Average) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry including rubbing and polishing etc. complete (single stone is to be used for risers and treads of steps and width of stone for skirting and dado shall be equal to the height of skirting & dado and length of 1.0 m). Granite stone black	13.60	Sqm



Executive Engineer
Municipal Corporation
Bhilai



Assistant Engineer
Municipal Corporation
Bhilai



Sub Engineer
Municipal Corporation
Bhilai