


MUNICIPAL CORPORATION OF BHILAI

NIT

जोन क्र. 04 अंतर्गत सार्वजनिक भवनों/मंचों का संधारण तथा शिवाजी नगर जोन कार्यालय में शौचालय संधारण कार्य।

(As Per PWD Building SOR 01.01.2015, Electrical SOR 01.06.2020 & NON SOR ITEM)

S.N.	PARTICULERS OF ITEMS	Quantity	UOM	
1	Dismantling lime/ cement plaster or skirting at any height raking out joints and cleaning the surface for plaster including disposal of rubbish within 50 metres lead.	170.00	Sqm	
2	Dismantling terrazzo or mosaic or glazed vitreous or patent cement or tiled flooring or dado skirting of any thickness without sub base.	70.00	Sqm	
3	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	70.00	Sqm	
4	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 40 mm thick	40.00	Sqm	
5	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)	170.00	Sqm	
6	Providing and applying 2mm thick ready mix exterior grade putty (Manufactured with cow dung processing) on walls to make the surface smooth and even.	300.00	Sqm	
7	Painting exterior surface with SMOOTH exterior emulsion paint manufactured with th cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with : On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over)	350.00	Sqm	
8	Wall painting with premium emulsion (plastic) manufactured with the cow dung processing emulsion paint of required shade to give an even shade. On new work (two or more coats)	350.00	Sqm	
9	Applying one coat of cement primer on wall surface (applied @ 0.80 litres/10 sqm) complete.	350.00	Sqm	
10	Add Extra For Electricfication, Water Supply & Sanitation Work.	53619.00	LS	
				Rate
11	<u>NON SOR ITEM</u> Office Chair Non-revolving and non-tilting chair with armrest	25	Each	
12	<u>NON SOR ITEM</u> Almirah Steel shelving cabinets	2	Each	


Executive Engineer
Municipal Corporation
Bhilai


Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai