


MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 15 वैशालीनगर थाना जिला दुर्ग मे वार्डब्रेट तार (काँटा तार) फेंसिंग पोल सहित बाउण्ड्री निर्माण कार्य ।

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.		
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	109.45	Cum
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	16.62	Cum
4	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size) + Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	44.060	Cum
5	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	14.900	Cum
6	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels. for: (A) Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	5896.86	Kg
(B)	Columns, Pillars, Piers and likes- rectangular or square in shape	152.88	Sqm
(C)	Beams, lintels, cantilevers & walls	117.60	Sqm
7	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	78.40	Sqm
8	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	50.80	Cum
9	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 + Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	7.84	Cum
)	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)	64.21	Cum
)	Providing and making 15mm thick cement plaster of mix: In Cement mortar 1:5 (1 cement : 5 fine sand)	392.00	Sqm

N.	PARTICULARS OF ITEMS	Quantity	Unit
		392.00	
2	Painting exterior surface with SMOOTH exterior emulsion paint manufactured with th cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with : On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over)	784.00	Sqm
3	Structural steel work in single section including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. As Per Qty. of 12mm + 15 mm Thick Plaster	1081.80	kg
	Providing and fixing in position G.I. barbed wire (93.8gram/m) to concrete/wooden/ angle iron posts (straight or diagonal) including securing and screwing with G.I. tying wire, G.I. stapples, G.I.U-nails or steel pins etc., complete (Cost of posts, struts to be paid for separately)	1176.00	Cum Km
	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm. Plain/ normal coloured precast interlock concrete block	196.00	Sqm Cum



ASSTT. ENGINEER
Nagar Palik Nigam, Bhilai



SUB-ENGINEER
Nagar Palik Nigam, Bhilai