


NAGAR PALIK NIGAM BHILAI


NIT

वार्ड क्र.-21 कैलाश नगर एवं 24 हाउसिंग बोर्ड में जर्जर रोड, नाली एवं पुलिया का संधारण कार्य।

(As per P.W.D BUILDING/ROAD S.O.R. W.E.F. 01.01.2015)

S.N.	PARTICULAR	Q	U
1	Excavation for all types and sizes of foundations, trenches and drains o.....m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil		
		40.32	cum
2	Providing and laying nominal mix cement concrete with crushed form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
		5.76	cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using .. reinforcement and form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		13.08	cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:Thermo-Mechanically treated bars FE 415		
		915.60	Kg
5	Providing and fixing formwork including entering Foundations, footings, base of columns and plinth beam in any shape and size.		
		133.80	sqm
6	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		1.20	cum
7	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads		
	P.C.C. M-10		
		7.50	cum
	P.C.C. M-25		
		33.75	cum
8	Carriage by mechanical transport upto 5 km lead:		
	Earth	36.29	cum


Executive
ASST ENGINEER
Nagar Palik Nigam, Bhilai


SUB ENGINEER
Nagar Palik Nigam, Bhilai