

**MUNICIPAL CORPORATION BHILAI (C.G.)**  
**NIT**

कार्य का नाम :- वार्ड-17 नेहरू भवन चिंगरी पारा पॉपुलर इंजि.वर्क्स से इन्द्रकुमार घर के आस-पास सड़क निर्माण कार्य।

PwD Building /Road Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads) P.C.C. M-10	44.70	Cum
1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads) P.C.C. M-25	161.55	Cum
2	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	12.24	Cum
3	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	25.20	Cum
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	2.40	Cum
5	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings: base of columns and plinth beam in any shape and size	70.00	Sqm
6	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	15.12	Cum
7	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars	1360.80	KG

8	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	3.04	Cum
9	Carriage by mechanical transport for 5 km lead.	12.24	Cum

**Executive Engineer  
Municipal Corporation  
Bhilai (C.G)**

*for* **Asstt. Engineer**  
**Municipal Corporation  
Bhilai (C.G)**

**Sub. Engineer**  
**Municipal Corporatio  
Bhilai (C.G)**