

MUNICIPAL CORPORATION OF BHILAI


NIT


(3)

कार्य का नाम :- वार्ड क्रमांक 30 स्वास्थ्य कार्यालय के सामने पेवर ब्लॉक लगाने का कार्य।

As Per PWD Building SOR 01.01.2015

| S.N | Item Code | PARTICULERS OF ITEMS | Quantity | UOM | Rate | Amount |
|-----|----------------------|---|----------|-----|---------|-----------|
| 1 | P-9 1.2 | Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area)In all types of soil | 1200.00 | Sqm | 7.20 | 8640.00 |
| 2 | P-23 3.1.2 | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size) | 45.00 | Cum | 2659.00 | 119655.00 |
| 3 | P-120 12.65. 2 | Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks | 1200.00 | Sqm | 632.00 | 758400.00 |
| 4 | P-23 3.1.5 | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | 3.38 | Cum | 4073.00 | 13746.00 |


 सहायक अभियन्ता
 नगर पालिक निगम, भिलाई


 उप अभियन्ता
 नगर पालिक निगम, भिलाई