

24  
MUNICIPAL CORPORATION BHILAI  
NIT

6

बर्ड 32 त्रिलोकीनाथ पांडेय के निवास से रमा विश्वकर्मा के घर तक आर.सी.सी. रोड एवं नाली निर्माण कार्य।

As Per PWD ROAD/ Building SOR 01.01.2015

SN.	Details of Item	Qty.	Unit
<b>CC Road (ROAD SOR)</b>			
1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads)P.C.C. M-10 Road SOR6.6.(I)	20.25	Cum
2	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads ) P.C.C. M-25 @ Rs. Road SOR6.6 III	99.90	Cum
<b>RCC Drain (Building SOR)</b>			
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	4.00	Cum
2	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	4.00	Cum
3	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	3.60	Cum
4	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	96.00	Cum
5	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	9.60	Cum
6	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	48.05	Cum
7	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding ..... as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	3363.36	Kg
8	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	7.56	Cum
9	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	270.24	Sqm
10	Carriage by mechanical transport for 5 km lead. Earth	106.88	Cum

सहस्रक अभियन्ता  
नगर पालिक निगम, भिलाई

उप अभियन्ता  
नगर पालिक निगम, भिलाई