


1

## MUNICIPAL CORPORATION BHILAI NIT

कार्य का नाम :- वार्ड 55 सेक्टर 02 पूर्व हनुमान मंदिर के समीप पेवर ब्लॉक एवं विद्युत  
संधारण कार्य।

*PWD Building 1.1.2015 Electrical SOR 1.6.2020*

Item No.	Particulars of item	Qty.
1	2	3
1	Supplying of following 230/250 volts LED Flood light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 15 KV surge protection on pole bracket, including connection, earthing, Seperate housing for driver etc complete as per specification and P.A. should be greater than 0.9. LED chip efficacy ratio $\geq 120$ lumens /watt.	6.00
2	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, wire in concealed FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5) 3 X 2.5 sq. mm in 20mm conduit	50.00
3	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	54.00
4	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	18.00
5	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	18.00
6	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks	180.00
7	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	3.28
8	Carriage by mechanical transport upto 5 km lead:Earth	43.20

  
उप अभियन्ता  
नगर पालिक निगम, भिलाई

सहायक अभियन्ता  
नगर पालिक निगम, भिलाई