

MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम :- पार्षद निधि अंतर्गत वार्ड 30 प्रगति नगर क्षेत्रांतर्गत अंबेडकर नगर एवं एकता नगर के क्षेत्रों में पाईप लाईन विस्तारीकरण कार्य।

As Per PWD Building SOR 01.01.2015,

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
1	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:		
a	15mm dia. nominal bore	5.00	M
b	20mm dia. nominal bore	10.00	M
c	25mm dia. nominal bore	15.00	M
2	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	0.98	Cum
3	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	1.59	Cum
4	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement.50 mm thick	1.33	Sqm
5	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)	5.10	Sqm
8	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	2000.00	Ltr

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई