


(3)


MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम – जलकार्य विभाग के शिवनाथ इंटेकवेल में ट्रांसफार्मर संधारण कार्य।

S.N.	PARTICULARS OF ITEMS	UOM	Quantity	Rate	Amount
1	Rewinding of HV copper coil 24 nos@20.7kg (in kg)	kg	501		
2	Reinsulation of LV copper coil 3 nos @ 134.8kg (in.kg)	kg	400		
3	Winding of complete LV & HV copper coil @ 901.2 kg (in kg.)	kg	901.2		
4	Replacement of Insulation (in kg)	kg	230		
5	Replacement of gasket & packing (per job)	Job	1		
6	Ovening of core-coil assembly for demoisturising	Job	1		
7	Routine testing as per IS:2026	Job	1		
8	Filtration of Trasformer Oil (in ltrs.)	Ltrs.	2700		
9	Labour charges for unloading of trasformer, detanking of core-coil assembly, dismantling of core-coil assembly, recore-coil assembly, retanking, refitting, & loading etc.	Job	1		


सहायक अभियंता
जलकार्य
नगर पालिक निगम,भिलाई


उप अभियंता
जलकार्य
नगर पालिक निगम, भिलाई