

# NAGAR PALIK NIGAM

## SCHEDULE OF ITEM

कार्य का नाम:- पार्श्व निधि अंतर्गत वार्ड 21 कुरुद में नेतराम गली के पास सी.सी. रोड एवं नाली निर्माण कार्य।

(As per P.W.D Road / Building SOR w.e.f -01.01.2015)

S.No.	DETAILS OF ITEM	UNIT	QTY.
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	Cum	24.10
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	Cum	0.90
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	Cum	2.40
3	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	Kg	100.00
4	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	Sqm	10.00
5	<b>Providing and laying cement concrete</b> for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads) P.C.C. M-30	Cum	40.50

  
ASSISTENT ENGINEER

MUNICIPAL CORPORATION,  
BHILAI

SUB ENGINEER

MUNICIPAL CORPORATION,  
BHILAI