

MUNICIPAL CORPORATION BHILAI


NIT

वार्ड क्र. 42 गौतम नगर, श्रीराम वाटिका के पास सामुदायिक भवन में नयी सुविधाओं का व्यवस्था करने का कार्य। (पार्षद निधि)

(As Per PWD Building/Road SOR 01.01.2015, Electrical SOR 01.06.2020 & NON SOR ITEM)

S.N.	PARTICULERS OF ITEMS	Quantity	UOM	
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	18.00	Cum	
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	1.80	Cum	
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	4.45	Cum	
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	380.16	Kg	
5	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:	6.72		
(A)	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	18.24	Sqm	
6	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	4779.20	Kg	
7	Steel work in tubular (round, square or rectangular hollow tubes etc.) structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, ---bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer. Electric resistance or induction butt welded tubes Grade-250	220.00	Kg	
8	Human and other sculptures (a) 5 to 7 feet	1	Each	
9	Add 3% for Electrification Work	14008.00	LS	
				Rate
10	<u>NON SOR ITEM</u> Providing & Fixing Ahuja's 100 Watt wired Outdoor Speaker.	10	Each	
11	<u>NON SOR ITEM</u> Providing & Fixing Ahuja's Amplifier with Bluetooth with all necessary cable connection.	1	Each	
12	<u>NON SOR ITEM</u> Providing & Fixing Ahuja's Unidirectional dynamic micro phone corded mic.	1	Each	
13	<u>NON SOR ITEM</u> Providing and fixing of FLAG at size of 3.0x2.0 with necessary arrangements and requirements	1	Each	


Executive Engineer
Municipal Corporation
Bhilai
नगर पालिक निगम, भिलाई


Assistant Engineer
Municipal Corporation
Bhilai-4
नगर पालिक निगम, भिलाई


Sub Engineer
Municipal Corporation
Bhilai
नगर पालिक निगम, भिलाई