

NAGAR PALIK NIGAM BHILAI

NIT

वार्ड क्र.-19 राजीव नगर गुरुद्वारा के सामने गुरुनानक नगर में नाली संधारण कार्य।
(As per P.W.D BUILDING S.O.R. W.E.F. 01.01.2015)

S.N.	PARTICULAR	Q	U
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	14.40	cum
2	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	2.00	cum
3	Excavation for all types and sizes of foundations, trenches and drains 0.....m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	56.00	cum
4	Providing and laying nominal mix cement concrete with crushed form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	14.00	cum
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using .. reinforcement and form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	30.00	cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	1350.00	Kg
7	Providing and fixing formwork including entering Foundations, footings, base of columns and plinth beam in any shape and size.	320.00	sqm
8	Carriage by mechanical transport upto 5 km lead: Earth	39.20	cum


ASSTT. ENGINEER

Nagar Palik Nigam, Bhilai


SUB ENGINEER

Nagar Palik Nigam, Bhilai

