
MUNICIPAL CORPORATION OF BHILAI

वार्ड क्र. 48 जोन-03 खुर्सीपार स्थित सामुदायिक लोधी भवन के समीप एक नग बोर खनन सह पाईप लाईन विस्तारीकरण कार्य।

(As Per PWD Building SOR 01.01.2015 & Electrical SOR 01.06.2020 & NON SOR ITEM)

s.N.	PARTICULERS OF ITEMS	Quantity	UOM
I	Carrying out the resistivity survey by VES method using Schlumberger configuration for locating the proper spot for drilling of tube well within the selected habitation, including photography, interpretation of resistivity data and submission of report in the desired format along with resistivity readings, necessary graph and photographs. (only successful point is payable)	J	Point
2	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer—in-charge upto 90 metre depth below ground level.		
	All types of soil 125 mm nominal dia	25.00	Metre
	Rocky strata including Boulders 125 mm nominal dia	65.00	Metre
3	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer—in-charge beyond 90 metre & upto 150 metre depth below ground level.		
	Rocky strata including Boulders 125 mm nominal dia	15.00	Metre
4	Supplying, assembling, lowering and fixing in vertical position in bore well, ISI marked G.I. casing pipe (Plain) medium class in 4 to 7 meters length one end fitted with socket as per IS: 1239 (Part-1&Part-2) 1992 with IVth revision (Up-to-date amendments), of reputed & approved make, including required hire & labour charges, fittings & accessories, all complete, for all depths, as per direction of Engineer- incharge.		
_	125 mm nominal dia	26.00	Metre
5	Development of tube well in accordance with IS: 2800 (part I) and IS: 11189, to establish maximum rate of usable water yield without sand content (beyond permissible limit), with required capacity air compressor, running the compressor for hire & labour charges of air compressor, tools & accessories etc., all as per requirement and direction of Engin-charge.	4.00	Hrs
6	Providing and fixing suitable size threaded mild steel cap or spot welded plate to the top of bore well housing/ casing pipe, removable as per requirement, all complete for bore well of: 125 mm nominal dia	1	Each
7	Electrical SOR 01.06.2020 Supplying, installation, testing and commissioning of submersible pump set for water supply system with submersible motor directly coupled to multi-stage submersible pump of specified discharge capacity, head, delivery size in existing bore well including 2 sets of suitable size holding clamps made out of 50 mm X 6 mm MS flat, connection with suitable submersible cable of standard length etc. as per specification and IS: 694 (2010).	1	Each
	Supply, installation, testing and commissioning of 5-7.5 HP 3 phase submersible motor starter cum control wall/ floor mounted type made out of not less than 1.6 mm thick MS sheet and comprising of following panel mounting switchgears there in including connection inter-connection etc. as per specification.		Fa-1
8	a) Phase indicating lamps with fuses and toggle switches 1 set b) 5/7.5 HP 3 phase DOL starter with over load and no volt relay 1 No c) 32 A "C" curve TPMCB 1 No		Each
	d) Voltmeter 0-500 V with selector switch 1 set e) Ammeter 0-10 A with CT's and selector switch 1 set.		





		Quantity	
S.N.	Providing following size ISI marked FR PVC insulated, PVC sheathed, 3 core submersible copper conductor wire and IS: 604 (2010)	70.00	Metre
١.	Providing following size ISI marked FR PVC insulated, PVC sheathed, 3 cole storm	,	
9			
	2.5 sq. mm Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including		
10	Providing and laying in trenches G.I. pipes medium class complete with G.F. Hand	35.00	Metre
-	excavation of trenches, refilling the same and testing of joints complete.	25.00	Metre
a	50 mm dia. nominal bore		Metre
b	40 mm dia. nominal bore	30.00	Metre
_ c	25 mm dia. nominal bore	15.00	Metre
d	20 mm dia. nominal bore	15.00	Metre
e	15 mm dia, nominal bore		7.1
11	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end):	2	Each
a	50 mm dia. nominal bore	2	Each
b	40 mm dia. nominal bore	3	Each
С	25 mm dia. nominal bore		
12	Providing and fixing G.I. Union in G.I. pipe (New work) including cutting and threading the pipe and		
12	making long screws etc. complete:	2	Each
a	50 mm dia. nominal bore	2	Each
ь	40 mm dia. nominal bore	3	Each
С	25 mm dia. nominal bore	3	Buen
13	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: Bib cock (250 grams)	10	Each
14	NON SOR ITEM P/F Panel box of size 36"x24"x12" made with 1 mm thick MS sheet framed with angle section 35x35x5 foot of panel box made with angle section 40x40x5 i/c grouting with cement concrete 1:1.5:3 mating providing of 18 mm ply sheet for fixing of electrical panel inner side i/c painting with satin synthetic enamel paint complete.	1	Each

Executive Engineer

Municiapal Corporation

Bhilai

Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer

Municipal Corporation

Bhilai