

MUNICIPAL CORPORATION OF BHILAI


NIT

महापौर निधि से वार्ड क्र. 51 पार्श्व निवास के पास गली से जी.ई. रोड़ सर्विस रोड़ तक नाली सहित नवीन सीमेंट कांक्रीट मार्ग निर्माण कार्य।

(AS Per PWD Building/Road SOR 01.01.2015)

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads)		
	P.C.C. M-10	15.75	Cum
	P.C.C. M-25	112.88	Cum
2	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	1.20	Cum
3	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	9.55	Cum
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	1.30	Cum
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1.5:3(1 cement : 1.5 coarse sand : 3 graded stone aggregate 20mm nominal size)	5.84	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	436.00	Kg
7	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	3.15	Cum
8	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	31.50	Sqm
9	Carriage by mechanical transport for 5 km lead. Earth	10.75	Cum

Executive Engineer
Municipal Corporation
Bhilai


Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer
Municipal Corporation
Bhilai