


MUNICIPAL CORPORATION BHILAI (C.G.)


NIT

कार्य का नाम :- वार्ड-17 चिंगरीपारा सार्वजनिक शौचालय के पास नाली संधारण कार्य।

Pwd Building /Road Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	108.50	Cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	15.50	Cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1.5:3	35.65	Cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	2317.25	KG
5	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	310.00	Sqm
6	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	15.50	Cum
7	Carriage by mechanical transport for 5 km lead.	108.50	Cum


Executive Engineer
Municipal Corporation
Bhilai (C.G)


Asstt. Engineer
Municipal Corporation
Bhilai (C.G)

Sub. Engineer
Municipal Corporatio
Bhilai (C.G)