

7

MUNICIPAL CORPORATION BHILAI
NIT

कार्य का नाम :- जोन 03 क्षेत्रांतर्गत पार्षद निधि अंतर्गत वार्ड क्रमांक 30 एकता नगर में
चबूतरा निर्माण कार्य।

Based on PWD/SOR 1-01-2015 (Building Works)

Item No.	Particulars of item	Qty.	Unit
1	2	3	4
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils. Chabutra	0.72	m ³
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	0.24	m ³
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). SOR Item No. 3.2.1	3.48	m ³
4	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	2.25	m ³
5	15mm thick Marble stone slab flooring over 18mm (Average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry including grinding rubbing and polishing etc. complete. (Area of slab should be 0.50 sqm and above) Makrana white second quality.	16.25	sqm

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई