MUNICIPAL CORPORATION BHILAI
NIT

कार्य का नाम :– वार्ड क्रमांक 33 संतोषी पारा जनजागरण मंच का संधारण कार्य।

Based on PWD/SOR 1-01-2015 (building works)

Item No.	Particulars of item	Qty.	Unit
1	2	7	7
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.In cement mortar.	1.00	Cum
2	Demolishing cement concrete including disposal of material within 50 metre lead.1:3:6 or richer mix	0.20	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth levelexcluding cost of form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mmnominal size).	3.00	Cum
4	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) SOR Item No 7.5.4	2.00	Cum
5	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating eachdeposited layer by ramming and watering, including dressing etc. complete.	3.00	Cum
6	Providing and making 15mm thick cement plaster of mix In Cement Mortar 1:6 (1 cement : 6 fine sand)	20.00	Sqm
7	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS: 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	30.00	Sqm
8	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS: 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	22.00	Sqm

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियंता
नगर पालिक निगम, भिलाई