

MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम :- वार्ड क्र. 69 सेक्टर 09 के विभिन्न स्थानों में सीमेंटीकरण सहित नाली निर्माण कार्य।

SN.	Details of Item	Qty.	Unit
1	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	138.00	Cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	9.000	Cum
3	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	220.00	Sqm
4	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	22.00	Sqm
5	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	9.00	Cum
6	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	78.60	Cum
7	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	8.40	Cum
8	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	1100.00	Kg
9	Carriage by mechanical transport for 5 km lead.	50.40	Cum
10	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) P.C.C. M-10	48	Cum


Asst Engineer
Municipal Corporation
Bhilai(C.G.)

Sub Engineer
Municipal Corporation
Bhilai(C.G.)