

# MUNICIPAL CORPORATION OF BHILAI

## NIT

वार्ड क्र. 38 सी मार्ट में सुरक्षा हेतु बिल्डिंग में लगे ग्लास के सामने ग्रिल लगाने का कार्य।

As Per PWD Building SOR 01.01.2015

SN	PARTICULARS OF ITEMS	QTY.	UNIT
1	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	3832.50	Kg
2	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	0.24	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	0.24	Cum
4	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	127.75	Sqm

  
Executive Engineer  
Municipal Corporation  
Bhilai

Assistant Engineer  
Municipal Corporation  
Bhilai

Sub Engineer  
Municipal Corporation  
Bhilai