

NAGAR NIGAM BHILAI

NIT

Name of work: - Repairing of Hand Pump with Material at Zone 04

AS PER ITEM RATE

S.NO	PARTICULAR	QTY	UNIT	RATE
1	Replacement of old Handpump and Providing and placing in position India Mark II hand pump complete with all accessories (riser pipe and plunger rod to be paid separately).	2	Each	
2	Construction of PCC platform as per describe drawing & design with all required materials pertaining to it minimum 1.5 meter dia.	2	Each	
	Providing & fixing of Hand Pump Material. Of ISI Mark Branded Company as per Specification			
3	जी.आई. पाईप 32 एम.एम.	525	Mtr.	
4	हैण्ड पंप राड (कनेक्टींग रॉड 10फिट)	220	Nos.	
5	सिलैण्डर सेट (<i>Made of Brass Metal as per Specification</i>)	38	Nos.	
6	पाईन्ट सेट (अपर वाल्व असेम्बली)	63	Nos.	
7	लोवर सेट (लोवर वाल्व असेम्बली)	55	Nos.	
8	बेयरिंग	125	Nos.	
9	चैन	125	Nos.	
10	हैण्ड पंप स्टैंड	6	Nos.	
11	माउथ	12	Nos.	
12	कर्वेशन हेड	12	Nos.	
13	हेण्डल सेट	6	Nos.	
14	एक्सल	140	Nos.	
15	लेदर ब्रेकेट	500	Nos.	
16	राड सॉकेट	255	Nos.	
17	नटबोल्ट (2')	230	kg	
18	जी.आई. निष्पल (32mm) - 6"	50	Nos.	
19	जी.आई. रेड्यूसर (40X32mm)	50	Nos.	
20	जी.आई. सॉकेट (32mm)	140	Nos.	
21	Repairing of Hand Pump only Above Ground Level	180	Nos.	
22	Repairing of Hand Pump Below Ground Level including Top maintance work complete.	600	Nos.	
23	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	2.00	Cum	


Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai