MUNICIPAL CORPORATION BHILAI (C.G.) NIT

कार्य का नाम :- पार्षद निधि से वार्ड-17 नेहरू भवन वार्ड अंतर्गत विभिन्न स्थानों में बोर खनन कार्य एवं

No.	Description and details of work	Qty.	Unit
1	Carrying out the resistivity survey by VES method using Schlumberger configuration for locating the proper spot for drilling of tube well within the selected habitation, including photography, interpretation of resistivity data and submission of report in the desired format along with resistivity readings, necessary graph and photographs. (only successful point is payable)	3.00	Point
2	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer—in-charge upto 90 metre depth below ground level. 150 mm dia.	75.00	Metre
	Rocky strata including Boulders. 150 mm dia.	225.00	Metre
3	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer—in-charge beyond 90 metre & upto 150 metre depth below ground level. Rocky strata including Boulders. 150 mm nominal dia	120.00	Metre
4	Providing and fixing suitable size threaded mild steel cap or spot welded plate to the top of bore well housing/ casing pipe, removable as per requirement, all complete for bore well of: 150 mm nominal dia	3.00	Each
5	Supplying, assembling, lowering and fixing in vertical position in bore well, ISI marked G.I. casing pipe (Plain) medium class in 4 to 7 meters length one end fitted with socket as per IS: 1239 (Part-1&Part-2) 1992 with IVth revision (Up-to-date amendments), of reputed & approved make, including required hire & labour charges, fittings & accessories, all complete, for all depths, as per direction of Engineer- in-charge.	90.00	Metre
6	Supplying, installation, testing and commissioning of submersible pump set for water supply system with submersible motor directly coupled to multistage submersible pump of specified discharge capacity, head, delivery size in existing bore well including 2 sets of suitable size holding clamps made out of 50 mm X 6 mm MS flat, connection with suitable submersible cable of standard length etc. as required. 2.0 Hp Single Phase	3.00	Each

S.No.	Description and details of work	Qty.	Unit
7	Supply, installation, testing and commissioning of 1-3 HP 1 phase submersible motor starter cum control wall/ floor mounted type made out of not less than 1.6 mm thick MS sheet and comprising of following panel mounting switchgears there in including connection inter-connection etc. as required. a) Phase indicating lamps with fuses and toggle switches 1 set b) 1/2/3 HP 1 phase DOL starter with over load and no volt relay 1 No c) 25 A "C" curve DPMCB 1 No d) Voltmeter 0-250 V 1 set e) Ammeter 0-10 A 1 set	3.00	Each
8	Supplying and laying following sizes one number PVC insulated/ XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade in existing RCC/ HUME/ STONEWARE/ METAL/ HDPE pipe as required.	300.00	Metre
	NON SOR ITEM		
1	Providing ISI Mark 32 mm dia Black H.D.P.E Roll Pipe with Bottom and Top Socket Assembly Fiting all Complete	300.00	Metre
2	3 phase energy meter connection with 4 Core 16mm Service Cable Inculding all installation Charge	3.00	Nos

Executive Engineer Municipal Corporation Bhilai (C.G)

Asstt. Engineer Municipal Corporation Bhilai (C.G)

Sub. Engineer Municipal Corporatio Bhilai (C.G)