

MUNICIPAL CORPORATION OF BHILAI


NIT


वार्ड 01 जुनवानी श्री रेसीडेन्सी से PMAY होते चौहान ग्रीनवेली फेस-02 तक पानी निकासी हेतु हयूम पाईप बिछाने का कार्य।

As Per PWD Building SOR 01.01.2015 & W.E.F. 01.01.2015

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	15.00	Cum
2	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	210.00	Cum
3	Labour only for laying and Jointing non-pressure (NP3) RCC socket & spigot pipes with rubber gasket joint including testing of joints 600 mm dia	75.00	Per Meter
4	Providing and Laying non-pressure (NP3) RCC socket & spigot pipes with rubber gasket joint including testing of joints. 600 mm dia	34.00	Per Meter

Executive Engineer
Municipal Corporation
Bhilai (C.G)


Asstt. Engineer
Municipal Corporation
Bhilai (C.G)


Sub. Engineer
Municipal Corporation
Bhilai (C.G)